

**NOTES:**

1. THIS SURVEY AND MAP HAS BEEN PREPARED IN ACCORDANCE WITH SECTIONS 20-300B-1 THRU 20-300B-20 OF THE REGULATIONS OF CONNECTICUT STATE AGENCIES - "STANDARDS FOR SURVEYS AND MAPS IN THE STATE OF CONNECTICUT" AS ENDORSED BY THE CONNECTICUT ASSOCIATION OF LAND SURVEYORS, INC. AND ADOPTED ON SEPT. 26, 1996. AMENDED ON OCTOBER 26, 2018.
2. THE TYPE OF SURVEY PERFORMED WITH RESPECT TO THE BOUNDARY PERIMETER IS IMPROVEMENT LOCATION MAP.
3. THE BOUNDARY DETERMINATION CATEGORY IS DEPENDENT RESURVEY.
4. WITH RESPECT TO HORIZONTAL ACCURACY, THIS MAP CONFORMS TO AN ACCURACY CLASS A-2.
5. WITH RESPECT TO VERTICAL ACCURACY OF V-2, THIS MAP CONFORMS TO A TOPOGRAPHIC ACCURACY CLASS T-2.
6. UTILITY, STRUCTURES, AND FACILITY LOCATIONS DEPICTED AND NOTED HEREON HAVE BEEN COMPILED, IN-PART, BY FIELD LOCATIONS OF OBSERVABLE STRUCTURES AND PAINTED MARKINGS. THE ACTUAL LOCATION AND SIZE OF UNDERGROUND UTILITIES SHOWN HEREON MAY NOT BE INDICATED. ADDITIONAL UNDERGROUND UTILITIES MAY EXIST. PRIOR TO EXCAVATION OR CONSTRUCTION, CONTACT "CALL BEFORE YOU DIG", (800) 922-4455.
7. OWNER OF RECORD: GRACIOUS PROPERTIES, LLC, RECORDED IN VOLUME 927, PAGE 108 IN THE TOWN OF WOODBRIDGE TOWN CLERK'S OFFICE.
8. THIS SITE IS NOT WITHIN A FEMA FLOOD HAZARD ZONE PER FEMA FIRM MAP 09009C0409J, EFFECTIVE DATE 5/16/2017.
9. ALL DECLARATIONS ARE VALID FOR THE MAP AND COPIES THERE OF ONLY IF THEY BEAR THE EMBOSSED SEAL OF THE SURVEYOR WHOSE SIGNATURE APPEARS HEREON. UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS SURVEY RENDER ANY DECLARATION SHOWN HEREON NULL AND VOID.

**MAP REFERENCES:**

- A. "RIGHT OF WAY PLAN SHOWING EASEMENTS TO BE ACQUIRED FROM CONGREGATION B'NAI JACOB BY THE CONNECTICUT LIGHT & POWER COMPANY, TOWN OF WOODBRIDGE, NEW HAVEN COUNTY, CONNECTICUT" DATED JULY 6, 2010, ON FILE AS MAP 720 IN THE TOWN OF WOODBRIDGE LAND RECORDS.
- B. "CONNECTICUT STATE HIGHWAY DEPARTMENT RIGHT OF WAY MAP, TOWN OF WOODBRIDGE, RIMMON ROAD FROM BEECHER ROAD EASTERLY TO THE ANSONIA ROAD", DATED 6/14/1940, SCALE 1"=40', ON FILE AS MAP 140 IN THE TOWN OF WOODBRIDGE LAND RECORDS.

N/F  
MINDONG, LI QIU  
ZHENG  
VOL 827, PG. 117

Rev	Date	Description
2	1/19/2026	Wetland Flag 20
1	10/21/2025	Name Change

THIS MAP IS NOT VALID UNLESS IT HAS A LIVE SIGNATURE AND EMBOSSED SEAL OF KEVIN M. CROWLEY.


TO MY KNOWLEDGE AND BELIEF, THIS MAP IS SUBSTANTIALLY CORRECT TO THE STANDARDS OF CLASS "A2" AS NOTED HEREON.

KEVIN M. CROWLEY  
R.L.S. # 70261

27 BEECHER ROAD  
WOODBRIDGE, CONNECTICUT

PREPARED FOR:  
**BEECHER ROAD, LLC**

SCALE 1" = 40' 24 JANUARY 2025  
FE24-1928






525 JOHN STREET  
BRIDGEPORT, CT.  
PH. 203-333-9465  
EMAIL: INFO@FULLERSURVEYORS.COM



1. THIS PLAN IS FOR THE PROPOSED 100 UNIT RESIDENTIAL BUILDING WITH PARKING, UTILITIES, AND MISCELLANEOUS SITE IMPROVEMENTS. THIS PLAN IS NOT TO BE USED AS A SITE OR CONSTRUCTION PLAN. ADDITIONAL DESIGN AND DETAILS ARE REQUIRED FOR BIDDING AND CONSTRUCTION.
2. THE CONTRACTOR SHALL LOCATE AND VERIFY THE SIZE, LOCATION, DEPTH AND INVERTS OF ANY AND ALL EXISTING UTILITIES PRIOR TO COMMENCING OPERATIONS. THE CONTRACTOR SHALL ALSO BE REQUIRED TO CONTACT THE TOLL FREE "CALL-BEFORE-YOU-DIG" PHONE NUMBER AT 1-800-922-4455.
3. THE PROPOSED DEVELOPMENT SHOWN HEREON WILL REQUIRE REVIEW AND APPROVAL BY THE VARIOUS AGENCIES OF WOODBRIDGE.
4. RESTORE ALL DISTURBED AREAS WITH A MINIMUM OF FOUR (4") INCHES OF TOPSOIL, SEED, AND HAY MULCH UPON COMPLETION OF CONSTRUCTION.
5. LOT SERVED BY TOWN SEWER SYSTEM AND PUBLIC WATER SUPPLY.
6. ANY ACTIVITY, PRESENT OR FUTURE, WHICH INVOLVES CLEARING, REGRADING, FILLING, CONSTRUCTION, OR ANY OTHER MEANS OF DISTURBANCE WITHIN THE WETLANDS OR THE 100' UPLAND REVIEW AREA IS PROHIBITED WITHOUT THE PRIOR CONSENT OF THE TOWN'S INLAND WETLAND AGENCY

A. LOCATION OF EXISTING OUT STRUCTURES, AND TOPOGRAPHY WERE OBTAINED FROM A SURVEY TITLED "IMPROVEMENT LOCATION PLAN, 27 BEECHER ROAD, WOODBRIDGE, CONNECTICUT, PREPARED FOR LUCIANI PROPERTIES, LLC", DATED 25 JANUARY 2025, SCALE 1"=50', BY FULLER ENGINEERING & LAND SURVEYING, LLC.



PROPOSED 100-UNIT MULTIFAMILY  
DEVELOPMENT  
27 BEECHER ROAD, WOODBRIDGE, CONNECTICUT  
PREPARED FOR  
BEECHER ROAD, LLC

Job Number:  
FE25-1960

Job Start Date:  
4-15-25

Rev	Date
Staff Comments	1/19/26
Level Spreader Mod	11/20/25
Issue IW	10/22/25

Drawn By: Checked By:  
D.R.R. J.E.Q.

Sheet Title:

PROPOSED SITE  
PLAN

Scale:  
1" = 40'

Sheet Number:

C-2.1



NOTES:



- THIS PLAN IS FOR THE PROPOSED 100 UNIT RESIDENTIAL BUILDING WITH PARKING, UTILITIES, AND MISCELLANEOUS SITE IMPROVEMENTS. THIS PLAN IS NOT TO BE USED AS A SITE OR CONSTRUCTION PLAN. ADDITIONAL DESIGN AND DETAILS ARE REQUIRED FOR BIDDING AND CONSTRUCTION.
- THE CONTRACTOR SHALL LOCATE AND VERIFY THE SIZE, LOCATION, DEPTH AND INVERTS OF ANY AND ALL EXISTING UTILITIES PRIOR TO COMMENCING OPERATIONS. THE CONTRACTOR SHALL ALSO BE REQUIRED TO CONTACT THE TOLL FREE "CALL-BEFORE-YOU-DIG" PHONE NUMBER AT 1-800-922-4455.
- THE PROPOSED DEVELOPMENT SHOWN HEREON WILL REQUIRE REVIEW AND APPROVAL BY THE VARIOUS AGENCIES OF WOODBRIDGE.
- RESTORE ALL DISTURBED AREAS WITH A MINIMUM OF FOUR (4") INCHES OF TOPSOIL, SEED, AND HAY MULCH UPON COMPLETION OF CONSTRUCTION.
- LOT SERVED BY TOWN SEWER SYSTEM AND PUBLIC WATER SUPPLY.
- ANY ACTIVITY, PRESENT OR FUTURE, WHICH INVOLVES CLEARING, REGRADING, FILLING, CONSTRUCTION, OR ANY OTHER MEANS OF DISTURBANCE WITHIN THE WETLANDS OR THE 100' UPLAND REVIEW AREA IS PROHIBITED WITHOUT THE PRIOR CONCENT OF THE TOWN'S INLAND WETLAND AGENCY

MAP REFERENCES:

- A. LOCATION OF EXISTING OUT STRUCTURES, AND TOPOGRAPHY WERE OBTAINED FROM A SURVEY TITLED "IMPROVEMENT LOCATION PLAN, 27 BEECHER ROAD, WOODBRIDGE, CONNECTICUT, PREPARED FOR LUCIANI PROPERTIES, LLC", DATED 25 JANUARY 2025, SCALE 1"=50', BY FULLER ENGINEERING & LAND SURVEYING, LLC.

SIGN LEGEND

A			B			C		
SIZES (IN)			SIZES (IN)			SIZES (IN)		
CONN DOT #			CONN DOT #			CONN DOT #		
SUPPORTS			SUPPORTS			SUPPORTS		
30"			12"x18"			12"x18"		
31-0552			12"x6"			12"x6"		
1			SEE ABOVE			SEE ABOVE		
1			1			1		



THIS DRAWING IS THE PROPERTY OF THE ENGINEER. IT HAS BEEN SPECIFICALLY PREPARED FOR THE OWNER FOR THIS PROJECT AT THIS SITE AND IS NOT TO BE USED FOR ANY OTHER PURPOSE, LOCATION OR OWNER WITHOUT WRITTEN CONSENT OF THE ENGINEER.

**FULLER ENGINEERING & LAND SURVEYING**  
525 JOHN STREET BRIDGEPORT, CT. 06604  
Office (203) 333-9495  
fax (203) 336-1769  
e-mail info@FullerSurveyors

**PROPOSED 100-UNIT MULTIFAMILY DEVELOPMENT**  
27 BEECHER ROAD, WOODBRIDGE, CONNECTICUT  
PREPARED FOR  
**BEECHER ROAD, LLC**

Job Number:  
FE25-1960

Job Start Date:  
4-15-25


Rev	Date
Staff Comments	1/19/26
Level Spreader Mod	11/20/25
Issue IW	10/22/25

Drawn By: Checked By:  
D.R.R. J.E.Q.


Sheet Title:  
**PROPOSED SITE PLAN ENLARGEMENT**

Scale:  
1" = 20'


Sheet Number:  
**C-2.2**









FIRE APPARATUS MOVEMENTS  
SCALE: 1"=30'



SU-30 MOVEMENTS  
SCALE: 1"=30'



SCHOOL BUS MOVEMENTS  
SCALE: 1"=30'



THIS DRAWING IS THE PROPERTY OF THE ENGINEER. IT HAS BEEN SPECIFICALLY PREPARED FOR THE OWNER FOR THIS PROJECT AT THIS SITE AND IS NOT TO BE USED FOR ANY OTHER PURPOSE, LOCATION OR OWNER WITHOUT WRITTEN CONSENT OF THE ENGINEER.

**FULLER ENGINEERING & LAND SURVEYING**  
525 JOHN STREET BRIDGEPORT, CT, 06604  
Office (203) 333-9485  
fax (203) 336-1769  
e-mail info@FullerSurveyors

PROPOSED 100-UNIT MULTIFAMILY DEVELOPMENT  
27 BEECHER ROAD, WOODBRIDGE, CONNECTICUT  
PREPARED FOR  
BEECHER ROAD, LLC

Job Number:  
FE25-1960

Job Start Date:  
4-15-25

Rev	Date
Staff Comments	1/19/25
Level Spreader Mod	11/20/25
Issue IW	10/22/25

Drawn By: Checked By:  
D.R.R. J.E.Q.

Sheet Title:  
VEHICLE  
MOVEMENT  
ANALYSIS

Scale:  
1"=20'

Sheet Number:  
C-2.3



NOTES:

1. THIS PLAN IS FOR THE PROPOSED 100 UNIT RESIDENTIAL BUILDING WITH PARKING, UTILITIES, AND MISCELLANEOUS SITE IMPROVEMENTS. THIS PLAN IS NOT TO BE USED AS A SITE OR CONSTRUCTION PLAN. ADDITIONAL DESIGN AND DETAILS ARE REQUIRED FOR BIDDING AND CONSTRUCTION.
2. THE CONTRACTOR SHALL LOCATE AND VERIFY THE SIZE, LOCATION, DEPTH AND INVERTS OF ANY AND ALL EXISTING UTILITIES PRIOR TO COMMENCING OPERATIONS. THE CONTRACTOR SHALL ALSO BE REQUIRED TO CONTACT THE TOLL FREE "CALL-BEFORE-YOU-DIG" PHONE NUMBER AT 1-800-922-4455.
3. THE PROPOSED DEVELOPMENT SHOWN HEREON WILL REQUIRE REVIEW AND APPROVAL BY THE VARIOUS AGENCIES OF WOODBRIDGE.
4. RESTORE ALL DISTURBED AREAS WITH A MINIMUM OF FOUR (4") INCHES OF TOPSOIL, SEED, AND HAY MULCH UPON COMPLETION OF CONSTRUCTION.
5. LOT SERVED BY TOWN SEWER SYSTEM AND PUBLIC WATER SUPPLY.
6. ANY ACTIVITY, PRESENT OR FUTURE, WHICH INVOLVES CLEARING, REGRADING, FILLING, CONSTRUCTION, OR ANY OTHER MEANS OF DISTURBANCE WITHIN THE WETLANDS OR THE 100' UPLAND REVIEW AREA IS PROHIBITED WITHOUT THE PRIOR CONSENT OF THE TOWN'S INLAND WETLAND AGENCY.
7. THE PROPOSED STORMWATER MANAGEMENT MEASURES TO BE INSTALLED ON THE SITE ARE TO BE CONSIDERED PERMANENT FIXTURES. THE PROPERTY OWNER IS RESPONSIBLE FOR THE STORMWATER MANAGEMENT MEASURES CONTINUED MAINTENANCE WITH THE PUBLISHED SCHEDULE, AND FOR THE PRESERVATION OF THEIR CONTINUED FUNCTIONALITY. THE STORMWATER MANAGEMENT MEASURES CANNOT BE FILLED IN, ABANDONED, LEFT IN DISREPAIR, OR OTHERWISE ALTERED WITHOUT THE PRIOR CONSENT OF THE TOWN OF WOODBRIDGE.
8. CERTIFICATION SHALL BE PROVIDED TO THE TOWN OF WOODBRIDGE BY THE DESIGN ENGINEER, PRIOR TO ISSUANCE OF A CERTIFICATE OF OCCUPANCY, THAT THE STORMWATER MANAGEMENT MEASURES WERE INSTALLED IN SUBSTANTIAL CONFORMANCE TO THE SITE PLAN OF RECORD, IN ACCORDANCE WITH THE OVERALL DESIGN INTENT.

MAP REFERENCES:

- A. LOCATION OF EXISTING OUT STRUCTURES, AND TOPOGRAPHY WERE OBTAINED FROM A SURVEY TITLED "IMPROVEMENT LOCATION PLAN, 27 BEECHER ROAD, WOODBRIDGE, CONNECTICUT, PREPARED FOR LUCIANI PROPERTIES, LLC", DATED 25 JANUARY 2025, SCALE 1"=50', BY FULLER ENGINEERING & LAND SURVEYING, LLC.

EARTHWORK CALCULATIONS



Cut/Fill Summary					
Name	Cut Factor	Fill Factor	2d Area	Cut	Fill
Cut/Fill	1.000	1.000	84857.51 Sq. Ft.	5752.35 Cu. Yd.	2743.59 Cu. Yd.
Totals			84857.51 Sq. Ft.	5752.35 Cu. Yd.	2743.59 Cu. Yd.

TEST PIT AND PERCOLATION DATA

PERCOLATION HOLE = 100-25			PERCOLATION HOLE = 100-25			PERCOLATION HOLE = 104-25			PERCOLATION HOLE = 105-25		
Depth = 49 IN			Depth = 40 IN			Depth = 42 IN			Depth = 40 IN		
Soak Test 1/2 hr			Soak Test 1/2 hr			Soak Test 1/2 hr			Soak Test 1/2 hr		
Time	Reading	Fall	Time	Reading	Fall	Time	Reading	Fall	Time	Reading	Fall
10:55 AM	8		2:14 PM	10		2:13 PM	8		2:14 PM	10	
11:05 AM	12	4	2:14 PM	15	5	2:20 PM	13	5	2:14 PM	17 1/8	2 1/8
11:15 AM	16	4	2:14 PM	17 1/8	2 1/8	2:30 PM	13	3 1/2	2:14 PM	17 1/8	2 1/8
11:25 AM	18 3/4	3 3/4	2:14 PM	18 1/4	1 1/8	2:33 PM	16 1/2	2	2:14 PM	18 1/4	1 1/8
11:35 AM	21 1/2	2 3/4	2:14 PM	19 1/4	1	2:43 PM	18 1/2	2	2:14 PM	19 1/4	1
11:45 AM	23 1/2	2	3:04 PM	20 1/4	1	2:43 PM	20 1/4	1 3/4	3:04 PM	20 1/4	1
11:55 AM	26	2 1/2	3:14 PM	20 3/4	1/2	3:09 PM	22	1 3/4	3:14 PM	20 3/4	1/2
Percolation Rate = 3 1/3 min./in			Percolation Rate = 5 4/7 min./in			Percolation Rate = 4 min./in			Percolation Rate = 5 4/7 min./in		
18 in/hr			10 3/4 in/hr			2.0 FT			10 3/4 in/hr		

DEEP TEST DT 101-25		DEEP TEST DT 102-25		DEEP TEST DT 103-25		DEEP TEST DT 104-25	
DEPTH	103 inches	DEPTH	105 inches	DEPTH	99 inches	DEPTH	78 inches
0-18"	Top soil	0-10"	Top soil	0-12"	Top soil	0-12"	Top soil
18-44"	Brown / Gray Loamy silt	10-37"	Brown / Gray Loamy sand	12-32"	Brown Silt Loam with roots	12-36"	Brown Silt Loam with some gravel
44-103"	Gray Fine - Medium sand with gravel and silt little cobbles	37-55"	Gray Fine - Medium sand with gravel and silt little cobbles with layers of coarse sand	32-52"	Gray sand and silt with some gravel	36-78"	Gray Sand and silt with gravel
103"	Ledge - Fractured Rock @ bottom	55-105"	Same with Some fragments of rock	52-99"	Gray sand and silt with some gravel Some fragments of rock	78"	Fractured Rock @ bottom
Mottling No	Water No	Mottling No	Water No	Mottling No	Water 99"	Mottling No	Water 99"
Ledge No	Ledge No	Ledge No	Ledge No	Ledge No	Ledge No	Ledge No	Ledge No

DEEP TEST DT 105-25		DEEP TEST DT 106-25		DEEP TEST DT 107-25		DEEP TEST DT 108-25	
DEPTH	54 inches	DEPTH	93 inches	DEPTH	87 inches	DEPTH	84 inches
0-12"	Top soil	0-18"	Top soil	0-12"	Top soil	0-12"	Top soil
12-26"	Brown Silt Loam	18-32"	Brown Silt Loam	12-47"	Brown Silt Loam	12-26"	Brown Silt Loam
26-47"	Gray Sandy silt with gravel	32-93"	Gray Silt with fine sand and some gravel Some fragments of rock	47-87"	Fractured Rock	26-46"	Sand and clay/silt with little of Fractured Rock
47-72"	Gray Sandy silt with gravel Some fragments of rock			46-84"	Fractured Rock		Fractured Rock
Mottling No	Water 48"	Mottling No	Water 87"	Mottling No	Water 60"	Mottling No	Water 75"
Ledge No	Ledge No	Ledge No	Ledge No	Ledge No	Ledge No	Ledge No	Ledge No



THIS DRAWING IS THE PROPERTY OF THE ENGINEER. IT HAS BEEN SPECIFICALLY PREPARED FOR THE OWNER FOR THIS PROJECT AT THIS SITE AND IS NOT TO BE USED FOR ANY OTHER PURPOSE, LOCATION OR OWNER WITHOUT WRITTEN CONSENT OF THE ENGINEER.

**FULLER ENGINEERING & LAND SURVEYING**  
525 JOHN STREET BRIDGEPORT, CT. 06604  
Office (203) 334-9485  
Fax (203) 336-1189  
e-mail info@FullerSurveyors

**PROPOSED 100-UNIT MULTIFAMILY DEVELOPMENT**  
27 BEECHER ROAD, WOODBRIDGE, CONNECTICUT  
PREPARED FOR  
**BEECHER ROAD, LLC**

Job Number:  
FE25-1960

Job Start Date:  
4-15-25

Rev	Date
Staff Comments	1/19/26
Level Spreader Mod	11/20/25
Issue IW	10/22/25

Drawn By: D.R.R.  
Checked By: J.E.Q.



Sheet Title:  
GRADING AND DRAINAGE PLAN

Scale:  
1" = 20'

Sheet Number:  
**C-3.1**



1. THIS PLAN IS FOR PERMITTING PURPOSES ONLY AND SHOULD NOT BE USED FOR CONSTRUCTION.
2. THE CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS, UTILITY LOCATIONS, AND INVERTS PRIOR TO CONSTRUCTION. ANY CONDITIONS FOUND TO DIFFER FROM THOSE SHOWN IN THE DRAWINGS SHALL BE IMMEDIATELY BROUGHT TO THE ATTENTION OF THE PROJECT ENGINEER.
3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR NOTIFYING UTILITY COMPANIES 72 HOURS PRIOR TO BEGINNING EXCAVATION.
4. GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TAP AND TIE ON FEES REQUIRED, AS WELL AS COST OF UNDERGROUND SERVICE CONNECTIONS TO THE BUILDING.
5. ALL TRENCHING, PIPE LAYING, AND BACKFILLING SHALL BE IN ACCORDANCE WITH FEDERAL OSHA REGULATIONS & AWC.
6. CONTRACTOR TO COORDINATE GAS MAIN, WATER, ELECTRIC, AND TELEPHONE INSTALLATION WITH APPROPRIATE UTILITY COMPANIES.
7. CONTRACTOR SHALL MAINTAIN A MINIMUM OF 3 FEET OF COVER FOR ALL UNDERGROUND ELECTRIC, TELEPHONE AND GAS UTILITIES.
8. CONTRACTOR SHALL MAINTAIN A MINIMUM OF 4.5 FEET OF COVER FOR ALL WATER DISTRIBUTION PIPING.
9. ALL NEW WATER LINES SHALL BE PRESSURE TESTED AND LEAKAGE TESTED IN ACCORDANCE WITH THE LATEST EDITION OF AWWA STANDARD C600 BY AWC.
10. ALL NEW WATER MAINS SHALL BE DISINFECTED IN ACCORDANCE WITH AWWA STANDARD C651 BY AWC.
11. ALL FIRE HYDRANTS SHALL BE PROVIDED WITH AN APPROVED GATE VALVE AT A MAXIMUM OF 5'-0" FROM HYDRANT.
12. ALL PIPE LENGTHS ARE HORIZONTAL DISTANCES AND ARE APPROXIMATE.
13. ALL WORK SHALL COMPLY WITH ALL APPLICABLE CODES, REGULATIONS, AND/OR LOCAL STANDARDS IMPOSED BY LOCAL UTILITY AUTHORITIES.
14. ALL MATERIAL SHALL BE APPROVED BY THE LOCAL UTILITY COMPANIES UNLESS DIRECTED OTHERWISE BY THE ENGINEER.
15. INFORMATION ON EXISTING UTILITIES AND STORM DRAINAGE SYSTEMS HAS BEEN COMPILED FROM AVAILABLE INFORMATION INCLUDING UTILITY PROVIDER AND MUNICIPAL RECORD MAPS AND/OR FIELD SURVEY AND IS NOT GUARANTEED CORRECT OR COMPLETE. UTILITIES AND STORM DRAINAGE SYSTEMS ARE SHOWN TO ALERT THE CONTRACTOR TO THEIR PRESENCE AND THE CONTRACTOR IS SOLELY RESPONSIBLE FOR DETERMINING ACTUAL LOCATIONS AND ELEVATIONS OF ALL UTILITIES AND STORM DRAINAGE SYSTEMS INCLUDING SERVICES. PRIOR TO DEMOLITION OR CONSTRUCTION, THE CONTRACTOR SHALL CONTACT "CALL YOU BEFORE YOU DIG" 72 HOURS BEFORE COMMENCEMENT OF WORK AND VERIFY ALL UTILITY AND STORM DRAINAGE SYSTEM LOCATIONS.
16. THRUST BLOCKS SHALL BE PROVIDED AT ALL TEES, ELBOWS, BENDS AND PLUGS OF SUFFICIENT SIZE TO COMPLY WITH MINIMUM STANDARDS OF N.F.P.A. - EXISTING SOIL CONDITIONS.
6. ANY ACTIVITY, PRESENT OR FUTURE, WHICH INVOLVES CLEARING, REGRADING, FILLING, CONSTRUCTION, OR ANY OTHER MEANS OF DISTURBANCE WITHIN THE WETLANDS OR THE 100' UPLAND REVIEW AREA IS PROHIBITED WITHOUT THE PRIOR CONSENT OF THE TOWN'S INLAND WETLAND AGENCY



THIS DRAWING IS THE PROPERTY OF THE ENGINEER. IT HAS BEEN SPECIFICALLY PREPARED FOR THE OWNER FOR THIS PROJECT AT THIS SITE AND IS NOT TO BE USED FOR ANY OTHER PURPOSE, LOCATION OR OWNER WITHOUT WRITTEN CONSENT OF THE ENGINEER.



25 JOHN STREET BRIDGEPORT, CT. 06604  
Office (203) 333-9465  
fax (203) 336-1769  
e-mail [Info@FullerSurveyors](mailto:Info@FullerSurveyors)

PROPOSED 100-UNIT MULTIFAMILY  
DEVELOPMENT  
227 BEECHER ROAD, WOODBRIDGE, CONNECTICUT  
PREPARED FOR  
BEECHER ROAD, LLC

Job Number:  
FE25-1960

Job Start Date:  
4-15-25

Rev	Date
Staff Comments	1/19/26
Level Spreader Mod	11/20/25
Issue IW	10/22/25

Drawn By: Checked By:  
D.R.R. J.E.Q.

Sheet Title:

PROPOSED  
UTILITIES  
PLAN

Scale:  
1" = 20'

Sheet Number:

## C-3.2



NOTES:

1. THIS PLAN IS FOR THE PROPOSED 100 UNIT RESIDENTIAL BUILDING WITH PARKING, UTILITIES, AND MISCELLANEOUS SITE IMPROVEMENTS. THIS PLAN IS NOT TO BE USED AS A SITE OR CONSTRUCTION PLAN. ADDITIONAL DESIGN AND DETAILS ARE REQUIRED FOR BIDDING AND CONSTRUCTION.
2. THE CONTRACTOR SHALL LOCATE AND VERIFY THE SIZE, LOCATION, DEPTH AND INVERTS OF ANY AND ALL EXISTING UTILITIES PRIOR TO COMMENCING OPERATIONS. THE CONTRACTOR SHALL ALSO BE REQUIRED TO CONTACT THE TOLL FREE "CALL-BEFORE-YOU-DIG" PHONE NUMBER AT 1-800-922-4455.
3. THE PROPOSED DEVELOPMENT SHOWN HEREON WILL REQUIRE REVIEW AND APPROVAL BY THE VARIOUS AGENCIES OF WOODBRIDGE.
4. RESTORE ALL DISTURBED AREAS WITH A MINIMUM OF FOUR (4") INCHES OF TOPSOIL, SEED, AND HAY MULCH UPON COMPLETION OF CONSTRUCTION.
5. LOT SERVED BY TOWN SEWER SYSTEM AND PUBLIC WATER SUPPLY.
6. EROSION CONTROL MEASURES SHOWN ARE SUGGESTED LOCATIONS. ACTUAL PLACEMENT OF PROPOSED EROSION CONTROL MEASURES TO BE DETERMINED IN THE FIELD IN CONSULTATION WITH THE DESIGN ENGINEER PRIOR TO COMMENCEMENT OF CONSTRUCTION.
7. ALL WORK PERFORMED BY THE OWNER / DEVELOPER MUST INCLUDE IMPLEMENTATION OF AN APPROVED SOIL EROSION AND SEDIMENTATION PLAN IN ACCORDANCE WITH PUBLIC ACT No. 83-385 [PASSED BY THE CONNECTICUT GENERAL ASSEMBLY]. THE OWNER / DEVELOPER SHALL BE THOROUGHLY FAMILIAR WITH THE CONNECTICUT GUIDELINES FOR EROSION AND SEDIMENT CONTROL.
8. SEE SHEET C-4.2 FOR DETAILED SOIL EROSION AND SEDIMENT CONTROL NOTES AND DETAILS.
6. ANY ACTIVITY, PRESENT OR FUTURE, WHICH INVOLVES CLEARING, REGRADING, FILLING, CONSTRUCTION, OR ANY OTHER MEANS OF DISTURBANCE WITHIN THE WETLANDS OR THE 100' UPLAND REVIEW AREA IS PROHIBITED WITHOUT THE PRIOR CONCENT OF THE TOWN'S INLAND WETLAND AGENCY.
7. SILT FENCE EQUALS LIMITS OF DISTURBANCE. SILT FENCE SHALL BE LOCATED IN FIELD BY A LICENSED LAND SURVEYOR PRIOR TO THE START OF CONSTRUCTION. CERTIFICATION SHALL BE PROVIDED TO THE TOWN OF PLAN COMPLIANCE WITH THE CLEARING LIMITS AND WITH THE EROSION AND SEDIMENTATION CONTROL MEASURES DESCRIBED HEREON.

MAP REFERENCES:

- A. LOCATION OF EXISTING OUT STRUCTURES, AND TOPOGRAPHY WERE OBTAINED FROM A SURVEY TITLED "IMPROVEMENT LOCATION PLAN, 27 BEECHER ROAD, WOODBRIDGE, CONNECTICUT, PREPARED FOR LUCIANI PROPERTIES, LLC", DATED 25 JANUARY 2025, SCALE 1"=50', BY FULLER ENGINEERING & LAND SURVEYING, LLC.



SEDIMENT BASIN CALCULATIONS

SEDIMENT TRAP	CONTRIBUTING AREA	CY Required	CF Required	CY Provided	CF Provided
1	.6 AC	76 CY	2,045 CF	83 CF	2,233 CF
2	1.7 AC	227 CY	6,135 CF	228 CF	6,157 CF
<b>TOTAL</b>	<b>2.3 AC</b>	<b>303 CY</b>	<b>8,181 CF</b>	<b>311 CF</b>	<b>8,390 CF</b>

**TOTAL SEDIMENT TRAP STORAGE CAPACITY** 8,390 CF

NOTE

TEMPORARY SEDIMENT TRAPS HAVE BEEN SIZED TO PROVIDE A MINIMUM STORAGE VOLUME OF 134 CUBIC YARDS PER ACRE OF DRAINAGE ARE PER THE 2002 CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL



THIS DRAWING IS THE PROPERTY OF THE ENGINEER. IT HAS BEEN SPECIFICALLY PREPARED FOR THE OWNER FOR THIS PROJECT AT THIS SITE AND IS NOT TO BE USED FOR ANY OTHER PURPOSE, LOCATION OR OWNER WITHOUT WRITTEN CONSENT OF THE ENGINEER.

**Fuller Engineering & Land Surveying**  
525 JOHN STREET BRIDGEPORT, CT. 06604  
Office (203) 333-9465  
fax (203) 338-1769  
e-mail info@FullerSurveyors

**PROPOSED 100-UNIT MULTIFAMILY DEVELOPMENT**  
27 BEECHER ROAD, WOODBRIDGE, CONNECTICUT  
PREPARED FOR  
**BEECHER ROAD, LLC**

Job Number:  
FE25-1960

Job Start Date:  
4-15-25

Rev	Date
Staff Comments	1/19/25
Level Spreader Mod	11/20/25
Issue IW	10/22/25

Drawn By: Checked By:  
D.R.R. J.E.Q.

Sheet Title:  
**EROSION & SEDIMENT CONTROL PLAN**

Scale:  
1" = 30'

Sheet Number:  
**C-4.1**



SOIL EROSION & SEDIMENTATION CONTROL NOTES:

SEDIMENT & EROSION CONTROL NARRATIVE

THE SEDIMENT AND EROSION CONTROL PLAN WAS DEVELOPED TO PROTECT THE EXISTING ROADWAY AND STORM DRAINAGE SYSTEMS, ADJACENT PROPERTIES, AND ANY ADJACENT WETLAND AREA AND WATER COURSE FROM SEDIMENT LADEN SURFACE RUNOFF AND EROSION.

ALL CONSTRUCTION ACTIVITIES INVOLVING THE REMOVAL OR DISTURBANCE OF SOILS ARE TO BE PROVIDED WITH APPROPRIATE PROTECTIVE MEASURES TO MINIMIZE EROSION AND CONTAIN SEDIMENT DISPOSITION WITHIN THE AREA UNDER DEVELOPMENT. THE MINIMUM STANDARD FOR INDIVIDUAL MEASURES SHALL BE THOSE OUTLINED IN THE "CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENTATION CONTROL, PUBLICATION DATE SEPTEMBER 30, 2023, EFFECTIVE DATE MARCH 30, 2024, AS AMENDED TO DATE. THOSE METHODS DEEMED MOST EFFECTIVE FOR THIS PROJECT ARE DESCRIBED HEREIN.

THE DIRECTIVES WITHIN THESE NOTES ARE GENERALIZED IN NATURE AND SOME MEASURES MAY NOT BE APPLICABLE TO THE SPECIFIC REQUIREMENTS OF THIS PROJECT. SEE THE OVERALL SOIL EROSION AND SEDIMENTATION CONTROL PLAN FOR THE SPECIFIC MEASURES REQUIRED.

CONSTRUCTION SCHEDULE

THE ANTICIPATED STARTING DATE FOR CONSTRUCTION IS FALL 2025 WITH COMPLETION ANTICIPATED BY DECEMBER 2025. APPROPRIATE EROSION CONTROL MEASURES AS DESCRIBED HEREIN, SHALL BE INSTALLED BY THE CONTRACTOR PRIOR TO THE COMMENCEMENT OF ALL SITE CLEARING OR CONSTRUCTION ACTIVITY. SCHEDULE WORK TO MINIMIZE THE LENGTH OF TIME THAT BARE SOIL WILL BE EXPOSED.

- CONSTRUCTION SEQUENCE
1. INSTALLATION OF SEDIMENT AND EROSION CONTROLS
  2. CLEARING AND GRUBBING OPERATIONS
  3. INSTALLATION OF DIVERSION BERMS AND SEDIMENT BASIN
  4. STRIPPING AND STOCKPILING OF TOPSOIL
  5. ROUGH GRADING
  6. INSTALLATION OF LEVEL SPREADER
  7. FINAL FILL OPERATIONS IF SUBSOIL IMPORT IS REQUIRED
  8. FOUNDATION / BUILDING CONSTRUCTION
  9. INSTALLATION OF SITE UTILITIES
  10. INSTALLATION OF PAVEMENTS AND CURBING
  11. INSTALLATION OF LANDSCAPE AND LIGHTING
  12. SITE STABILIZATION
  13. REMOVAL OF SEDIMENT AND EROSION CONTROLS AFTER APPROVAL BY THE MUNICIPALITY.

CONTINGENCY EROSION PLAN

THE CONTRACTOR SHALL INSTALL ALL SPECIFIED EROSION CONTROL MEASURES AND WILL BE REQUIRED TO MAINTAIN THEM IN THEIR INTENDED FUNCTIONING CONDITION. THE AGENTS OF THE MUNICIPALITY INLAND WETLANDS COMMISSION AND/OR PROJECT ENGINEER SHALL HAVE THE AUTHORITY TO REQUIRE SUPPLEMENTAL MAINTENANCE OR ADDITIONAL MEASURES IF FIELD CONDITIONS ARE ENCOUNTERED BEYOND WHAT WOULD NORMALLY BE ANTICIPATED.

OPERATION REQUIREMENTS

- CLEARING AND GRUBBING OPERATIONS:
1. ALL SEDIMENTATION AND EROSION CONTROL MEASURES, INCLUDING THE CONSTRUCTION OF TEMPORARY SEDIMENTATION TRAPS WILL BE INSTALLED PRIOR TO THE START OF CLEARING AND GRUBBING OPERATIONS.
  2. FOLLOWING INSTALLATION OF ALL SEDIMENTATION AND EROSION CONTROL MEASURES, THE CONTRACTOR SHALL NOT PROCEED WITH GRADING, FILLING OR OTHER CONSTRUCTION OPERATIONS UNTIL THE ENGINEER HAS INSPECTED AND APPROVED ALL INSTALLATIONS.
  3. THE CONTRACTOR SHALL TAKE EXTREME CARE DURING CLEARING AND GRUBBING OPERATIONS SO AS NOT TO DISTURB UNPROTECTED WETLAND AREAS OR SEDIMENTATION AND EROSION CONTROL DEVICES.
  4. FOLLOWING THE COMPLETION OF CLEARING AND GRUBBING OPERATIONS, ALL AREAS SHALL BE STABILIZED WITH TOPSOIL AND SEEDING OR PROCESSED AGGREGATE STONE AS SOON AS PRACTICAL.

- ROUGH GRADING OPERATIONS:
1. DURING THE REMOVAL AND/OR PLACEMENT OF EARTH AS INDICATED ON THE GRADING PLAN, TOPSOIL SHALL BE STRIPPED AND APPROPRIATELY STOCKPILED FOR REUSE.
  2. ALL STOCKPILED TOPSOIL SHALL BE SEEDED, MULCHED WITH HAY, AND ENCLOSED BY A SILTATION FENCE.
  3. IN REGARD TO THE ROCK CUT RETAINING WALL CONSTRUCTION, DURING SITE EXCAVATION AND GRADING, SHOULD LEDGE ROCK PRESENT ITSELF IN THE LOCATION OF THE REAR RETAINING WALL, ITS EXPOSURE AS FINISHED GRADE MAY BE PERMITTED BY STAFF APPROVAL INSTEAD OF SOME OR ALL THE MASONRY BLOCK RETAINING WALL, SUBJECT TO SUBMISSION AND ACCEPTANCE OF A CERTIFIED REPORT FROM A CONNECTICUT LICENSED GEO-TECHNICAL ENGINEER BEING PROVIDED VERIFYING THAT THE EXPOSED LEDGE ROCK IS STABLE ENOUGH TO SUPPORT THE SLOPE. SAID REPORT SHALL INCLUDE RELATED CONSTRUCTION DETAILS, AS WELL AS DETAILS OF HOW THE SOIL AT THE TOP OF THE EXPOSED SLOPE WILL BE CONTAINED AND MAINTAINED IN THE LONG TERM TO PREVENT EROSION.

- FILLING OPERATIONS:
1. PRIOR TO FILLING, ALL SEDIMENTATION AND EROSION CONTROL DEVICES SHALL BE PROPERLY IMPLEMENTED, MAINTAINED AND FULLY INSTALLED, AS DIRECTED BY THE ENGINEER AND AS SHOWN ON THIS PLAN.
  2. AS GENERAL GRADING OPERATIONS PROGRESS, ANY TEMPORARY DIVERSION DITCHES SHALL BE RAISED OR LOWERED, AS NECESSARY, TO DIVERT SURFACE RUNOFF TO THE SEDIMENT BASINS.

- FINAL GRADING AND PAVING OPERATIONS:
1. NO CUT OR FILL SLOPES SHALL EXCEED 2:1 EXCEPT WHEN STABILIZED BY ROCK FACED EMBANKMENTS OR EROSION CONTROL BLANKETS, JUTE MESH AND VEGETATION. ALL SLOPES SHALL BE SEEDED, AND ANY ROAD OR DRIVEWAY SHOULDER AND BANKS SHALL BE STABILIZED IMMEDIATELY UPON COMPLETION OF FINAL GRADING UNTIL TURF IS ESTABLISHED.
  2. PAVEMENT SUB-BASE AND BASE COURSES SHALL BE INSTALLED OVER AREAS TO BE PAVED AS SOON AS FINAL SUB-GRADES ARE ESTABLISHED AND UNDERGROUND UTILITIES AND STORM DRAINAGE SYSTEMS HAVE BEEN INSTALLED.
  3. AFTER CONSTRUCTION OF PAVEMENT, TOPSOIL, FINAL SEED, MULCH AND LANDSCAPING, REMOVE ALL TEMPORARY EROSION CONTROL DEVICES ONLY AFTER ALL AREAS HAVE BEEN PAVED AND/OR GRASS HAS BEEN WELL ESTABLISHED AND THE SITE HAS BEEN INSPECTED AND APPROVED BY THE MUNICIPALITY, EASTERN CONNECTICUT SOILS CONSERVATION DISTRICT, INLAND WETLANDS COMMISSION.

INSTALLATION OF SEDIMENTATION AND EROSION CONTROL MEASURES

- I. SILTATION FENCE:
- A. DIG A SIX INCH TRENCH ON THE UPHILL SIDE OF THE DESIGNATED FENCE LINE LOCATION.
  - B. POSITION THE POST AT THE BACK OF THE TRENCH (DOWNHILL SIDE), AND HAMMER THE POST AT LEAST 1.5 FEET INTO THE GROUND.
  - C. LAY THE BOTTOM SIX INCHES OF THE FABRIC INTO THE TRENCH TO PREVENT UNDERMINING BY STORM WATER RUN-OFF.
  - D. BACKFILL THE TRENCH AND COMPACT.
- II. ANTI-TRACKING APRON (CONSTRUCTION ENTRANCE)
- A. CLEAR THE ENTRANCE OF ALL VEGETATION, ROOTS AND OTHER OBJECTIONABLE MATERIAL.
  - B. INSTALL SUBSURFACE DRAINAGE AT POORLY DRAINED AREAS.
  - C. INSTALL GEOTEXTILE IN A DIRECTION PARALLEL TO THE ENTRANCE.
  - D. PLACE STONES IN THE SPECIFIED DIMENSIONS AND THICKNESS AS DETAILED.
  - E. IF ENTRANCE EXCEEDS 2% GRADIENT, CONSTRUCT A WATER BAR WITHIN THE CONSTRUCTION ENTRANCE AT A MINIMUM INTERVAL OF 15 FEET.
- III. HAY BALE BARRIER
- A. EXCAVATE TRENCH AS WIDE AS THE BALES AND AT LEAST 4 INCHES DEEP.
  - B. WING EACH END OF TRENCH UPSLOPE SO THE BOTTOM OF LAST BALE IS HIGHER THAN THE LOWEST BALE IN THE BARRIER.
  - C. PLACE BALES IN A SINGLE ROW LENGTHWISE WITH ENDS BUTTED TIGHTLY.
  - D. ANCHOR BALES WITH AT LEAST TWO STAKES DRIVEN 18 INCHES MINIMUM INTO THE GROUND.
  - E. BACKFILL BALES WITH EXCAVATED MATERIAL TO A MINIMUM DEPTH OF 4 INCHES ON THE UPHILL SIDE OF THE BALE.
- IV. SILT SACK
- A. REMOVE GRATE FROM DRAINAGE STRUCTURE.
  - B. INSTALL SILT SACK PER MANUFACTURERS RECOMMENDATIONS.
  - C. INSPECT PERIODICALLY AND REMOVE ACCUMULATED MATERIALS AS NEEDED.

DIVERSION BERMS

- A. REMOVE ALL TREES, BRUSH, STUMPS, OBSTRUCTIONS, AND OTHER OBJECTIONABLE MATERIAL.
- B. EXCAVATE OR SHAPE TO THE LINE, GRADE, AND CROSS SECTION AS DETAILED ON THE PLAN.
- C. FILL VOIDS TO PREVENT UNEQUAL SETTLEMENT.
- D. STABILIZE AS DETAILED.

SEDIMENT TRAPS

- A. CLEAR GRUB, AND STRIP ANY VEGETATION AND ROOT MAT FROM ANY PROPOSED EMBANKMENT AND OUTLET AREA.
- B. REMOVE STONES AND ROCKS WITH A DIAMETER GREATER THAN 3 INCHES.
- C. EXCAVATE WET STORAGE AND CONSTRUCT EMBANKMENT AND/OR OUTLET AS REQUIRED TO ATTAIN THE SPECIFIED STORAGE REQUIREMENTS.
- D. USE ONLY FILL MATERIALS FREE FROM EXCESSIVE ORGANICS, DEBRIS, LARGE ROCKS OVER 6 INCHES, OR OTHER UNSUITABLE MATERIALS.
- E. COMPACT 9 INCH LAYERS WITH CONSTRUCTION EQUIPMENT.
- F. STABILIZE EMBANKMENTS AS SPECIFIED.

CONSTRUCTION DITCH

- A. CONSTRUCT DITCH TO HAVE AN UNINTERRUPTED POSITIVE GRADE TO AN OUTLET.
- B. DIVERTED RUNOFF FROM A DISTURBED AREA SHALL TERMINATE AT A SEDIMENT TRAPPING DEVICE.
- C. REMOVE ALL TREES, BRUSH, STUMPS, OBSTRUCTIONS OR OTHER OBJECTIONABLE MATERIAL WHICH IS IN CONFLICT WITH THE SWALE.
- D. EXCAVATE, SHAPE TO LINE, GRADE, AND CROSS-SECTION AS REQUIRED TO BE FREE OF BANK PROJECTIONS OR OTHER IRREGULARITIES WHICH WILL IMPEDE NORMAL FLOW.
- E. COMPACT FILLS BY EARTH-MOVING EQUIPMENT.
- F. STABILIZE FLOW CHANNEL PER DETAIL.
- G. INSPECT PERIODICALLY AND MAINTAIN AS REQUIRED.

CHECK DAM

- A. PLACE STONE ON FILTER FABRIC FOUNDATION TO THE LINES, GRADES, AND LOCATIONS SHOWN ON THE PLANS.
- B. SET SPACING OF CHECK DAMS TO ASSUME THAT ELEVATIONS OF THE CREST OF THE DOWNSTREAM DAM IS AT THE SAME ELEVATION OF THE TOE OF THE UPSTREAM DAM.
- C. EXTEND THE STONE A MINIMUM OF 1.5 FEET BEYOND THE DITCH BANKS TO PREVENT CUTTING AROUND THE DAM.
- D. PROTECT THE CHANNEL DOWNSTREAM OF THE LOWEST CHECK DAM FROM SCOUR AND EROSION WITH STONE OR LINERS AS APPROPRIATE.
- E. ENSURE THAT CHANNEL APPURTENANCES SUCH AS CULVERT ENTRANCES BELOW CHECK DAMS ARE NOT SUBJECT TO DAMAGE OR BLOCKAGE FROM DISPLACED STONE.

EARTH DIKE

- A. COMPACT WITH EARTH-MOVING EQUIPMENT.
- B. CREATE WITH POSITIVE DRAINAGE TO AN OUTLET.
- C. CONSTRUCT WITH WIDER TOP AND FLATTER SIDE SLOPES TO FACILITATE CROSSING WITH CONSTRUCTION EQUIPMENT.

OPERATION AND MAINTENANCE OF SEDIMENTATION AND EROSION CONTROL MEASURES

- I. SILTATION FENCE:
- A. ALL SILTATION FENCES SHALL BE INSPECTED AS A MINIMUM WEEKLY OR AFTER EACH RAINFALL. ALL DETERIORATED FABRIC AND DAMAGED POSTS SHALL BE REPLACED AND PROPERLY REPOSITIONED IN ACCORDANCE WITH THIS PLAN.
  - B. SEDIMENT DEPOSITS SHALL BE REMOVED FROM BEHIND THE FENCE WHEN THEY EXCEED A HEIGHT OF ONE FOOT.
- II. SEDIMENT TRAPS:
- A. CONTRACTOR TO KEEP WEEKLY CHECKLIST LOGS FOR INSPECTIONS OF ALL SEDIMENT AND EROSION CONTROL DEVICES AND HAVE THEM READILY AVAILABLE ON-SITE AT ALL TIMES FOR INSPECTION BY CT DEEP, LOCAL AUTHORITIES OR ENGINEER.
  - B. ALL SEDIMENT BASINS SHALL BE INSPECTED FOLLOWING EACH RAINFALL. REPAIR OF SLOPES SHALL BE PROMPTLY MADE AS NEEDED. EROSION CONTROL BLANKETS MAY BE USED FOLLOWING REPAIR OF SLOPE AS DIRECTED BY THE ENGINEER.
  - C. SEDIMENT DEPOSITS SHALL BE REMOVED FROM SEDIMENT BASINS AND/OR SEDIMENT TRAPS WHEN THEY EXCEED A HEIGHT OF ONE FOOT UNLESS OTHERWISE INDICATED ON THE EROSION CONTROL PLANS AND DETAILS TO BE AT A SPECIFIC ELEVATION PER CLEAN OUT MARKERS.
  - D. SEDIMENT SHALL BE DISPOSED OF ON-SITE OR AS DIRECTED BY THE ENGINEER AND LOCAL GOVERNING OFFICIALS. SEE SEDIMENT AND EROSION CONTROL NOTES HEREIN REGARDING DISPOSAL REQUIREMENTS FOR OFF SITE SPOIL DISPOSAL.
- III. CHECK DAMS:
- A. ALL STONE CHECK DAMS SHALL BE INSPECTED FOLLOWING EACH RAINFALL. REPAIR OF STONE CHECK DAMS SHALL BE PROMPTLY MADE AND ACCUMULATED SEDIMENT REMOVED WHEN IT REACHES ONE HALF OF THE HEIGHT OF THE CHECK DAM.
- IV. TEMPORARY/PERMANENT DRAINAGE SWALES:
- A. SWALES SHALL BE INSPECTED FOLLOWING EACH RAINFALL. REPAIR OF ANY WASHED OUT OR ERODED SLOPES SHALL BE MADE PROMPTLY AND THE AREA SHALL BE RE-SEEDED AS NECESSARY.
  - B. EROSION CONTROL BLANKETS MAY BE USED TO REPAIR ERODED SWALES AS DIRECTED BY THE ENGINEER OR MUNICIPALITY AGENT.
- V. SILT SACKS
- A. MONITOR, MAINTAIN, REMOVE, OR REPLACE SILT SACK AS REQUIRED TO ASSURE FREE DRAINAGE INTO EXISTING DRYWELL.
- VI. ANTI-TRACKING APRONS
- A. MAINTAIN FUNCTIONALITY OF ANTI-TRACKING APRON THROUGHOUT THE CONSTRUCTION PERIOD.
  - B. REMOVE, AND DISPOSE OF ACCUMULATED SEDIMENTS IMMEDIATELY IF THIS MEASURE SHOWS SIGNS NON-FUNCTIONALITY.

EROSION AND SEDIMENT CONTROL PLAN

1. SILTATION FENCE WILL BE INSTALLED AT ALL CULVERT OUTLETS IF CULVERT OUTLETS ARE APPLICABLE TO THIS PROJECT AND ALONG THE TOE OF ALL CRITICAL CUT AND FILL SLOPES.
2. CULVERT DISCHARGE AREAS WILL BE PROTECTED WITH RIP RAP CHANNELS, ENERGY DISSIPATORS WILL BE INSTALLED AS SHOWN ON THESE PLANS AND AS NECESSARY.
3. ALL EROSION AND SEDIMENT CONTROL MEASURES WILL BE INSTALLED IN ACCORDANCE WITH THE STANDARDS AND SPECIFICATIONS OF THE CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL MANUAL, LATEST EDITION.
4. EROSION AND SEDIMENT CONTROL MEASURES WILL BE INSTALLED PRIOR TO CONSTRUCTION WHENEVER POSSIBLE.
5. ALL CONTROL MEASURES WILL BE MAINTAINED IN EFFECTIVE CONDITION THROUGHOUT THE CONSTRUCTION PERIOD.
6. ADDITIONAL CONTROL MEASURES WILL BE INSTALLED DURING THE CONSTRUCTION PERIOD, IF NECESSARY OR REQUIRED OR AS DIRECTED BY THE CIVIL ENGINEER OR BY LOCAL GOVERNING OFFICIALS.
7. SEDIMENT REMOVED FROM EROSION CONTROL STRUCTURES WILL BE DISPOSED IN A MANNER WHICH IS CONSISTENT WITH THE INTENT AND REQUIREMENTS OF THE EROSION CONTROL PLANS, NOTES, AND DETAILS.

SEDIMENT AND EROSION CONTROL NOTES

1. THE OWNER IS RESPONSIBLE FOR IMPLEMENTING THIS SEDIMENT AND EROSION CONTROL PLAN. THIS RESPONSIBILITY INCLUDES THE PROPER INSTALLATION AND MAINTENANCE OF EROSION CONTROL MEASURES, INFORMING ALL PARTIES ENGAGED WITH CONSTRUCTION ON THE SITE OF THE REQUIREMENTS AND OBJECTIVES OF THIS PLAN, INFORMING THE GOVERNING AUTHORITY OR INLAND WETLANDS AGENCY OF ANY TRANSFER OF THIS RESPONSIBILITY, AND FOR CONVEYING A COPY OF THE SEDIMENT & EROSION CONTROL PLAN IF THE TITLE TO THE LAND IS TRANSFERRED.
2. AN EROSION CONTROL BOND MAY BE REQUIRED TO BE POSTED WITH THE MUNICIPALITY TO ENSURE IMPLEMENTATION OF THE EROSION CONTROL MEASURES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE POSTING OF THIS BOND AND FOR INQUIRIES TO THE MUNICIPALITY FOR INFORMATION ON THE METHOD, TYPE AND AMOUNT OF THE BOND POSTING UNLESS OTHERWISE DIRECTED BY THE OWNER.
  - A) A SUMMARY OF THE SITE CONDITIONS, E&S BMPS, AND COMPLIANCE; AND
  - B) THE DATE, TIME, AND THE NAME OF THE PERSON CONDUCTING THE INSPECTION
3. VISUAL SITE INSPECTIONS SHALL BE CONDUCTED WEEKLY, AND AFTER EACH MEASURABLE PRECIPITATION EVENT OF 0.10 INCHES OR GREATER BY QUALIFIED PERSONNEL, TRAINED AND EXPERIENCED IN EROSION AND SEDIMENT CONTROL, TO ASCERTAIN THAT THE EROSION AND SEDIMENT CONTROL (E&S) BMPS ARE OPERATIONAL AND EFFECTIVE IN PREVENTING POLLUTION. A WRITTEN REPORT OF EACH INSPECTION SHALL BE KEPT, AND INCLUDE:
  - A) A SUMMARY OF THE SITE CONDITIONS, E&S BMPS, AND COMPLIANCE; AND
  - B) THE DATE, TIME, AND THE NAME OF THE PERSON CONDUCTING THE INSPECTION
4. THE CONTRACTOR SHALL CONSTRUCT ALL SEDIMENT AND EROSION CONTROLS IN ACCORDANCE WITH THE CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL, PREPARED BY CTDEEP, LATEST EDITION IN ACCORDANCE WITH THE CONTRACT DOCUMENTS, AND AS DIRECTED BY THE MUNICIPALITY. THE CONTRACTOR SHALL KEEP A COPY OF THE GUIDELINES ON-SITE FOR REFERENCE DURING CONSTRUCTION.
5. ADDITIONAL AND/OR ALTERNATIVE SEDIMENT AND EROSION CONTROL MEASURES MAY BE INSTALLED DURING THE CONSTRUCTION PERIOD IF FOUND NECESSARY BY THE CONTRACTOR.

OWNER, CIVIL ENGINEER, THE MUNICIPALITY, EASTERN CONNECTICUT SOILS CONSERVATION DISTRICT, INLAND WETLANDS COMMISSION, OR GOVERNING AGENCIES. THE CONTRACTOR SHALL CONTACT THE OWNER AND APPROPRIATE GOVERNING AGENCIES FOR APPROVAL IF ALTERNATIVE CONTROLS OTHER THAN THOSE SHOWN ON THE PLANS ARE PROPOSED.

6. THE CONTRACTOR SHALL INSPECT ALL SEDIMENT AND EROSION CONTROLS BEFORE AND AFTER EACH STORM (0.10 INCHES OR GREATER RAINFALL), OR AT LEAST WEEKLY, TO VERIFY THAT THE CONTROLS ARE OPERATING PROPERLY AND MAKE REPAIRS WHERE NECESSARY.

7. THE CONTRACTOR SHALL KEEP A SUPPLY OF EROSION CONTROL MATERIAL (HAY BALES, SILT FENCE, JUTE MESH/RIP RAP ETC.) ON-SITE FOR MAINTENANCE AND EMERGENCY REPAIRS.

8. INSTALL PERIMETER SEDIMENT CONTROLS PRIOR TO CLEARING OR CONSTRUCTION. ALL CONSTRUCTION SHALL BE CONTAINED WITHIN THE LIMIT OF DISTURBANCE (LOD), WHICH SHALL BE MARKED WITH SILT FENCE, SAFETY FENCE, HAY BALES, RIBBONS, OR OTHER MEANS PRIOR TO CLEARING. CONSTRUCTION ACTIVITY SHALL REMAIN ON THE UPHILL SIDE OF THE SILT FENCE UNLESS WORK IS SPECIFICALLY CALLED FOR ON THE DOWNHILL SIDE OF THE FENCE.

9. TOPSOIL SHALL BE STRIPPED AND STOCKPILED FOR USE IN FINAL LANDSCAPING. ALL EARTH STOCKPILES SHALL HAVE HAY BALES OR SILT FENCE AROUND THE LIMIT OF PILE. PILES SHALL BE TEMPORARILY SEEDED IF PILE IS TO REMAIN IN PLACE FOR MORE THAN 7 DAYS.

10. SEDIMENTATION TRAPS SHALL PROVIDE 134 CUBIC YARDS OF SEDIMENT STORAGE PER DISTURBED ACRE CONTRIBUTING TO THE TRAP. PROVIDE TRAP VOLUMES FOR ALL DISTURBANCE ON SITE IF SPECIFIED.

11. MINIMIZE LAND DISTURBANCES. SEED AND MULCH DISTURBED AREAS WITH TEMPORARY MIX AS SOON AS PRACTICABLE (2 WEEK MAXIMUM UNSTABILIZED PERIOD) USING PERENNIAL RYEGRASS AT 40 LBS PER ACRE, MULCH ALL CUT AND FILL SLOPES AND SWALES WITH LOOSE HAY AT A RATE OF 2 TONS PER ACRE. IF NECESSARY, REPLACE LOOSE HAY ON SLOPES WITH EROSION CONTROL BLANKETS OR JUTE CLOTH. MODERATELY GRADED AREAS, ISLANDS, AND TEMPORARY CONSTRUCTION STAGING AREAS MAY BE HYDROSEDED WITH TACKIFIER.

12. EXCAVATED MATERIAL FROM TEMPORARY SILT TRAPS MUST BE STOCKPILED ON UPHILL SIDE OF SILT FENCE.

13. INSTALL SILT FENCE ACCORDING TO MANUFACTURER'S INSTRUCTION, PARTICULARLY, BURY LOWER EDGE OF FABRIC INTO GROUND PRIOR TO ANY WORK IN UPLAND AREAS. SILT FENCE SHALL BE MIRAFI ENVIROFENCE, AMMOCO SILT STOP OR EQUIVALENT APPROVED BY THE CIVIL ENGINEER. FILTER FABRIC USED SHALL BE MIRAFI 100X OR EQUIVALENT. SEE SPECIFICATIONS FOR FURTHER INFORMATION.

14. WHERE INDICATED ON EROSION CONTROL PLANS USE NEW HAY BALES AND REPLACE THEM WHENEVER THEIR CONDITION DETERIORATES BEYOND REASONABLE USABILITY. STAKE HAY BALES SECURELY INTO GROUND AND BUTT TIGHTLY TOGETHER TO PREVENT UNDERCUTTING AND BYPASSING.

15. INSTALL TEMPORARY DIVERSION DITCHES, PLUNGE POOLS, SEDIMENT TRAPS, AND DENATURING PITS AS SHOWN AND AS NECESSARY DURING VARIOUS PHASES OF CONSTRUCTION TO CONTROL RUNOFF UNTIL UPHILL AREAS ARE STABILIZED. LOCATION OF TEMPORARY SEDIMENT TRAPS WILL REQUIRE REVIEW AND APPROVAL BY THE CIVIL ENGINEER AND GOVERNING OFFICIAL.

16. BLOCK THE OPEN UPSTREAM ENDS OF DETENTION BASIN/SEDIMENTATION BASIN OUTLET CONTROL ORIFICE UNTIL SITE IS STABILIZED. CONVERT TEMPORARY SEDIMENT BASINS TO PERMANENT DETENTION BASINS ONCE SITE HAS BEEN STABILIZED. CLEAN OUTLET CONTROL STRUCTURES AS NECESSARY AND REMOVE ACCUMULATED SEDIMENT FROM BOTTOM OF BASIN. BLOCK END OF STORM SEWERS IN EXPOSED TRENCHES WITH BOARDS AND SANDBAGS AT THE END OF EACH WORKING DAY WHEN RAIN IS EXPECTED.

17. SWEEP AFFECTED PORTIONS OF OFF SITE ROADS ONE OR MORE TIMES A DAY (OR LESS FREQUENTLY IF TRACKING IS NOT A PROBLEM) DURING CONSTRUCTION. OTHER DUST CONTROL MEASURES TO BE USED AS NECESSARY INCLUDE WATERING DOWN DISTURBED AREAS, USING CALCIUM CHLORIDE, AND COVERING LOADS ON DUMP TRUCKS.


18. PERIODICALLY CHECK ACCUMULATED SEDIMENT LEVELS IN THE SEDIMENT TRAPS DURING CONSTRUCTION AND CLEAN ACCUMULATED SILT WHEN NECESSARY OR WHEN ONE FOOT OF SEDIMENT HAS ACCUMULATED OR PER SPECIFIC CLEANOUT MARKER ELEVATION. REMOVE ACCUMULATED SEDIMENT FROM BEHIND SILT FENCE WHEN LEVEL REACHES HALF THE HEIGHT OF THE HAY BALE OR ONE FOOT AT SILT FENCE. DISPOSE OF SEDIMENT LEGALLY EITHER ON OR OFF SITE.

19. IMMEDIATELY UPON DISCOVERING UNFORESEEN CIRCUMSTANCES POSING THE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION, THE OPERATOR SHALL IMPLEMENT APPROPRIATE BEST MANAGEMENT PRACTICES (BMP) TO ELIMINATE THE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION.

20. ALL EXCAVATED MATERIAL SHALL BE PLACED ON THE HIGH SIDE OF UTILITY AND STORM PIPE TRENCHES SO AS TO ALLOW THE TRENCH TO INTERCEPT ALL SILT LADEN RUNOFF.


21. AN AREA SHALL BE CONSIDERED TO HAVE ACHIEVED FINAL STABILIZATION WHEN IT HAS A MINIMUM OF 70% UNIFORM PERENNIAL VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER WITH A DENSITY SUFFICIENT TO RESIST ACCELERATED SURFACE EROSION AND SUBSURFACE CHARACTERISTICS SUFFICIENT TO RESIST SLIDING OR OTHER MOVEMENTS.

22. MAINTAIN ALL PERMANENT AND TEMPORARY SEDIMENT CONTROL DEVICES IN EFFECTIVE CONDITION THROUGHOUT THE CONSTRUCTION PERIOD. UPON COMPLETION OF WORK SWEEP PARKING LOT AND REMOVE ALL TEMPORARY SEDIMENT CONTROLS WHEN AUTHORIZED BY LOCAL GOVERNING AUTHORITY. FILE NOT (NOTICE OF TERMINATION) WITH GOVERNING AUTHORITY RESPONSIBLE FOR REGULATING STORM WATER DISCHARGES FROM CONSTRUCTION ACTIVITIES PER NPDES.




STOCKPILE AREA DETAIL

SCALE: NTS




STOCKPILE PROTECTION DETAIL

SCALE: NTS




SILT FENCE PROTECTION DETAIL

SCALE: NTS



SILT SACK INLET PROTECTION DETAIL


SCALE: NTS



TEMPORARY SEDIMENT TRAP

SCALE: N.T.S.

TEMPORARY SEDIMENT TRAP SHALL BE CONSTRUCTED PER "CONNECTICUT GUIDELINES FOR SOIL EROSION & SEDIMENT CONTROL, PUBLISHED SEPTEMBER 30, 2023, EFFECTIVE MARCH 30, 2024.




GRADATION TABLE			
	CONN. DOT 2" CRUSHED GRAVEL	ASTM C-33 NO. 2	ASTM C-33 NO. 3
SQUARE MESH SIEVES	% FINER	% FINER	% FINER
2 1/2 INCHES	100	90-100	100
2 INCHES	95-100	35-70	90-100
1 1/2 INCHES	35-70	0-15	35-70
1 1/4 INCHES	0-25	---	---
1 INCHES	0-10	---	0-15
3/4 INCHES	---	0-5	---
1/2 INCHES	---	---	0-5
3/8 INCHES	---	---	---

SOURCE: U.S. DEPARTMENT OF AGRICULTURE, SOIL CONSERVATION SERVICE, STORRS, CONNECTICUT.

TYP ANTI TRACKING APRON DETAIL

SCALE: N.T.S.



THIS DRAWING IS THE PROPERTY OF THE ENGINEER. IT HAS BEEN SPECIFICALLY PREPARED FOR THE OWNER FOR THIS PROJECT AT THIS SITE AND IS NOT TO BE USED FOR ANY OTHER PURPOSE, LOCATION OR OWNER WITHOUT WRITTEN CONSENT OF THE ENGINEER.



525 JOHN STREET BRIDGEPORT, CT. 06604  
OFFICE (203) 338-1465  
FAX (203) 338-1769  
e-mail Info@FullerSurveyors

PROPOSED 100-UNIT MULTIFAMILY DEVELOPMENT  
27 BEECHER ROAD, WOODBRIDGE, CONNECTICUT  
PREPARED FOR BEECHER ROAD, LLC

Job Number:

FE25-1960

Job Start Date:

4-15-25

Rev	Date
Staff Comments	1/19/26
Level Spreader Mod	11/20/25
Issue IW	10/22/25

Drawn By: D.R.R.  
Checked By: J.E.Q.

Sheet Title:  
EROSION & SEDIMENT CONTROL NOTES & DETAILS

Scale:

Sheet Number:

C-4.2



KEY	QTY	BOTANICAL NAME	COMMON NAME	ROOT SIZE	COMMENTS	
<b>TREES</b>						
AB	3	ABIES BALSAMEA	BALSAM FIR	B&B	10'-12" HT	FULL, EXTRA HEAVY
AR	6	ACER RUBRUM	RED MAPLE	B&B	2 1/2" CAL	FULL, EXTRA HEAVY, SINGLE STRAIGHT LEADER
<b>UNDERSTORY TREES</b>						
CC	1	CERCIS CANADENSIS	EASTERN REDBUD	B&B	2' CAL	FULL, EXTRA HEAVY, SINGLE STRAIGHT LEADER
CF	3	CORNUS FLORIDA	FLOWERING DOGWOOD	B&B	2' CAL	FULL, EXTRA HEAVY, SINGLE STRAIGHT LEADER
PC	4	PYRUS CALLERYANA 'ARISTOCRAT'	ARISTOCRAT PEAR	B&B	2 1/2" CAL	FULL, EXTRA HEAVY, SINGLE STRAIGHT LEADER
<b>UPLAND SHRUBS</b>						
AD	35	AZALEA 'DELAWARE VALLEY WHITE'	DELAWARE VALLEY WHITE AZALEA	CONT	24"-30" HT	FULL, EXTRA HEAVY
IC	110	ILEX GRENATA COMPACTA	COMPACT JAPANESE HOLLY	CONT	24"-30" HT	FULL, EXTRA HEAVY
IV	111	ILEX VERTICILLATA	WINTERBERRY	CONT	24"-36" HT	FULL, EXTRA HEAVY
RPJ	35	RHODODENDRON 'PJM'	PJM RHODODENDRON	CONT	24"-36" HT	FULL, EXTRA HEAVY
RR	24	RHODODENDRON 'ROSEUM ELEGANS'	ROSEUM ELEGANS RHODODENDRON	CONT	24"-36" HT	FULL, EXTRA HEAVY
VC	9	VACCINIUM CORYMBOSUM	HIGH-BUSH BLUEBERRY	CONT	24"-36" HT	FULL, EXTRA HEAVY

## GENERAL NOTES

- ## PLANTING SOIL NOTES

- ## GENERAL PLANTING NOTES

- PRUNING SHALL BE IN ACCORDANCE WITH APPROVED HORTICULTURAL STANDARDS IN ORDER TO PRESERVE THE NATURAL FORM OF THE SPECIFIC PLANTS. IF APPLICABLE & APPROVED BY THE LANDSCAPE ARCHITECT, ONE-FOURTH TO ONE-THIRD OF THE WOOD SHALL BE REMOVED BY THINNING OUT TO BALANCE ROOT LOSS DUE TO TRANSPLANTING.

CUT BURLAP AND WIRE BASKETS, REMOVE FROM TOP 1/3 OF ROOT BALL

3" BARK MULCH

3" SOIL, SAYER TYP, FINISHED GRADE

TOPSOIL SUBSOIL

PLANTING MIX MXTURE. SEE LANDSCAPE NOTES. EACH TREE TO BE PROVIDED A MINIMUM OF 1/2 C.F. OF LOAM INCORPORATED INTO SOIL

PLANTING MIXTURE

TOP OF EDGE

SET TOP OF ROOT AT OR SLIGHTLY FINISHED GRADE

SCALE OR IF P AUG.

18" MIN.


## TREE PLANTING

SCALE: NTS

- AREAS OF MASS PLANTING. CONTINUOUSLY EXCAVATE AND MULCH ENTIRE BED

## SHRUB / GROUNDCOVER PLANTING


SCALE: NTS



NEW ENGLAND WETLAND PLANTS, INC.			
14 Pearl Lane South Watford, MA 02475			
PHONE: 413-548-8800 FAX: 413-549-4800			
EMAIL: INFO@NEWP.COM WEB: ADDRESS: WWW.NEWP.COM			
New England Conservation/Wildlife Inc.			
Botanical Name		Common Name	Indicator
<i>Zizania aquatica</i>	Virginia Wild Rice		FACW
<i>Sagittaria arifolia</i>	Little Bluestem		FACU
<i>Andropogon gerardii</i>	Big Bluestem		FACU
<i>Fernex rubra</i>	Red Fern		FACU
<i>Scirpus americanus</i>	Indian Grass		UPL
<i>Scirpus atrovirens</i>	Switch Grass		FACU
<i>Chenopodium berlandieri</i>	Perennial Pigweed		FACU
<i>Dioscorea canadensis</i>	Shiny Tuckermint		
<i>Asclepias tuberosa</i>	Butterfly Milkweed		NI
<i>Rubus purpureus</i>	Boggar Tussock		FACW
<i>Eriophorum purpureum</i> ( <i>Eriophorum maculatum</i> )	Purple Joe Pye Weed		FAC
<i>Asclepias tuberosa</i>	Butterfly Milkweed		FACU
<i>Scirpus americanus</i> ( <i>Scirpus americanus</i> )	Heath or Hardy Arrow		UPL
<i>Sagittaria pifillifolia</i>	Early Goldenrod		

The New England Conservation/Wildlife Mix provides a permanent cover of grasses, wildflowers, and legumes. For both good erosion control and wildlife habitat value. The mix is designed to be a no maintenance seeding, and is appropriate for fill and slopes, detention basin side slopes, and disturbed areas adjacent to commercial and residential projects.

New England Wetland Plants, Inc. may modify seed mixes at any time depending upon seed availability. The design criteria and ecological function of the mix will remain unchanged. Price is \$/bush pound, FOB warehouse, plus SH and applicable taxes.



THIS DRAWING IS THE PROPERTY OF THE ENGINEER. IT HAS BEEN SPECIFICALLY PREPARED FOR THE OWNER FOR THIS PROJECT AT THIS SITE AND IS NOT TO BE USED FOR ANY OTHER PURPOSE, LOCATION OR OWNER WITHOUT WRITTEN CONSENT OF THE ENGINEER.



525 JOHN STREET BRIDGEPORT, CT. 06604  
Office (203) 333-9465  
fax (203) 336-1769  
e-mail [Info@FullerSurveyors](mailto:Info@FullerSurveyors)

PROPOSED 100-UNIT MULTIFAMILY  
DEVELOPMENT  
27 BEECHER ROAD, WOODBRIDGE, CONNECTICUT  
PREPARED FOR  
BEECHER ROAD, LLC

Job Number:  
FE25-1960

Job Start Date:	4-15-25
-----------------	---------

Rev	Date
Staff Comments	1/19/2
Level Spreader Mod	11/20/2
Issue IW	10/22/2

Drawn By: D.R.R.	Checked By: J.E.Q.
------------------	--------------------

Sheet Title:

LANDSCAPE  
PLAN

Scale:  
1"=20'


Sheet Number:

## C-5.1

1/20/2026 1:22 PM C 5.1 - Landscape.dwg




# Oil Separators




1250-1500 Capacity  
H2O Loading Design

LIQUID CAPACITY	Height H	Liquid B	Invert I
1250	5'4"	3'4"	4'1"
1500	6'0"	4'0"	4'9"




1. Minimum Concrete Compressive Strength: 4000 psi @ 28 days
2. Design Loading: AASHTO HS-20
3. Epoxy Coated Interior, Asphalt Coated Exterior
4. Monolithic Base & Walls
5. Top Slab Joint Sealed With Butyl Rubber
6. Connecticut DOT & DEP Approved
7. Interior Piping Supplied & Installed By Others

p. fenninger 12.17.07




TYP TRENCH DRAIN DETAIL

SCALE: N.T.S.




STORM CLEANOUT DETAIL

SCALE: N.T.S.




GATE VALVE DETAIL

SCALE: N.T.S.




PRECAST CONCRETE DISTRIBUTION BOX

NOT TO SCALE




SUBSURFACE STORM WATER RETENTION  
4'x4' PRE-CAST LEACHING GALLERY FIELD DETAIL

NOT TO SCALE



PRECAST STORM MANHOLE / CATCHBASIN


SCALE: N.T.S.



TYPICAL UTILITY TRENCH DETAIL


SCALE: N.T.S.

TYP OIL GRIT SEPARATOR



COARSE PARTICLE SEPARATOR

SCALE: N.T.S.




PUMP NOTES:

- 1 PUMP TO BE FLYGT 5.9 HP, MODEL No. 2630 3PH OR APPROVED EQUAL.
- 2 HIGH LEVEL ALARM TO WARNING LIGHT AND BUZZER TO WARN OF PUMP FAILURE
- 3 FORCE MAIN TO HAVE A MINIMUM OF 3' COVER
- 4 PUMP TO BE CONFIGURED TO RUN ALTERNATELY OR TOGETHER


TYP PUMP CHAMBER DETAIL

SCALE: N.T.S.




LEVEL SPREADER DETAIL

SCALE: N.T.S.



THIS DRAWING IS THE PROPERTY OF THE ENGINEER. IT HAS BEEN SPECIFICALLY PREPARED FOR THE OWNER FOR THIS PROJECT AT THIS SITE AND IS NOT TO BE USED FOR ANY OTHER PURPOSE, LOCATION OR OWNER WITHOUT WRITTEN CONSENT OF THE ENGINEER.



PROPOSED 100-UNIT MULTIFAMILY DEVELOPMENT  
27 BEECHER ROAD, WOODBRIDGE, CONNECTICUT  
PREPARED FOR  
BEECHER ROAD, LLC

Job Number:  
FE25-1960

Job Start Date:  
4-15-25

Rev	Date
Staff Comments	1/19/25
Level Spreader Mod	11/20/25
Issue IW	10/22/25


Drawn By: Checked By:  
D.R.R. J.E.Q.

Sheet Title:  
DETAIL SHEET

Scale:



Sheet Number:  
C-6.1






### CONCRETE SIDEWALK

SCALE: NTS




### SECTION OF CONCRETE DRIVEWAY APPROACH

SCALE: NTS




### STANDARD DUTY ASPHALT PAVING

### HEAVY DUTY ASPHALT PAVING




### PAVING DETAILS


SCALE: NTS




### CONTRACTION JOINT




### CONSTRUCTION JOINT



### CONSTRUCTION JOINT TO EXISTING PAVEMENT




### JOINT DETAIL BLOW-UP (TYP.)




### FLUSH CURB AT PAVEMENT

SCALE: NTS



### CONCRETE CURBING


DETAIL PER TOWN OF MONROE STANDARDS



### EXTRUDED BITUMINOUS CONCRETE LIP CURBING DETAIL

SCALE: NTS


DETAIL PER TOWN OF MONROE DPW STANDARD DRAWINGS



- NOTES
1. CONCRETE SHALL BE 3500 PSI AIR ENTRAINED AT A 4" SLUMP.
  2. TRANSVERSE CONTROL JOINTS 1/4" WIDE BY 3/4" DEEP, TO BE FORMED EVERY 4'.
  3. EXPANSION JOINTS WITH 1/2" PREMOLDED MATERIALS SHALL BE PLACED EVERY 28' TO FULL DEPTH.
  4. WEATHER PROTECTION AND CURING COMPOUNDS SHALL BE USED IN ACCORDANCE WITH CTDOT SPECIFICATIONS.
  5. ALL EDGES SHALL BE ROUNDED WITH A 1/4" EDGE TOOL.

### CURB TRANSITION DETAIL

SCALE: NTS



THIS DRAWING IS THE PROPERTY OF THE ENGINEER. IT HAS BEEN SPECIFICALLY PREPARED FOR THE OWNER FOR THIS PROJECT AT THIS SITE AND IS NOT TO BE USED FOR ANY OTHER PURPOSE, LOCATION OR OWNER WITHOUT WRITTEN CONSENT OF THE ENGINEER.

**Fuller Engineering & Land Surveying**  
525 JOHN STREET BRIDGEPORT, CT. 06604  
Office (203) 333-9465  
fax (203) 338-1769  
e-mail Info@FullerSurveyors

PROPOSED 100-UNIT MULTIFAMILY DEVELOPMENT  
27 BEECHER ROAD, WOODBRIDGE, CONNECTICUT  
PREPARED FOR  
BEECHER ROAD, LLC

Job Number:  
FE25-1960

Job Start Date:  
4-15-25

Rev	Date
ISSUED	XXX
Staff Comments	1/19/25
Level Spreader Mod	11/20/25
Issue IW	10/22/25

Drawn By: Checked By:  
D.R.R. J.E.Q.


Sheet Title:  
DETAIL SHEET

Scale:


Sheet Number:

C-6.2






SCALE: NTS



SCALE: NTS



SCALE: NTS




SCALE: NTS



SCALE: NTS





SCALE: NTS



SCALE: NTS



SCALE: NTS



Job Start Date:  
4-15-25

Drawn By: Checked By:  
D.R.R. J.E.Q.

Scale:

Sheet Number:

**C-6.3**